


## DSW-1 SIGNAL RELAY

The relay is designed for the F&F video intercoms. It activates an additional optical signaling (using light source) or sound signaling (using e.g. siren) at the time of the call from the gate station. At activation the contact switches every 1 sec. Duration can be adjusted in the range from 5 to 30 sec.



power supply	100÷265V AC
overload	2A
activation time - adjustable	5÷30sec
switching time on/off	1sec/1sec
power consumption standby/on	<0.2W/<0.6W
working temperature	-15÷50°C
terminal	2.5mm <sup>2</sup> screw terminals
dimensions	67×50×26mm
mounting	two screws to substrate
protection level	IP20

## CONNECTION SCHEME

